

Holdenhurst WRC

£30m investment to increase sewage treatment capacity, protect Bournemouth's beaches and meet the needs of the expanding population

by Joe Edmunds, Elizabeth Keen, Ben Norris, Tim Burt & Neil Allen

Holdenhurst Water Recycling Centre (WRC) is a Wessex Water facility situated near Bournemouth, Dorset. It is a large activated sludge works, which currently serves a total population of approximately 180,000 which significantly increases during the summer months. The WRC was identified by the Environment Agency in the Water Industry National Environment Programme (WINEP) as requiring process improvements, including the reduction of phosphorus levels in the treated wastewater prior to release to the River Stour, which then flows into Christchurch Harbour, and the provision of additional storm storage capacity.



IFAS steelwork installation - Courtesy of Trant Engineering

Regulatory obligations

The regulatory obligations include a phosphorus (Total P) permit of 1 mg/l during AMP7 and beyond. However, it was decided that additional investment would be made to enable the AMP7 works to meet the needs of the improved AMP8 0.8mg/l Total P stretch target. Key parameters for the treated flows are as follows.

Flow to full treatment	Total phosphorus	Iron 95% ile (mg/l)	Aluminium maximum
1424 l/s	0.8 mg/l	4 mg/l	3.6 mg/l

The obligations also include the requirement to provide an additional 9,000m³ of additional storm storage (increasing the total capacity to 29,800m³). Other requirements include Event Duration Monitoring (EDM).

Proposed solution

Phosphorus removal: Separate chemical dosing installations are to be provided for the two existing treatment streams within the site to achieve the phosphorus removal.

The chemical dosing will utilise polyaluminium chloride (PAC), which was selected to avoid the anticipated adverse impacts on the site's ultraviolet (UV) treatment plant which would arise from using ferric compounds.

Stormwater storage: Additional capacity is to be achieved by the construction of a new reinforced concrete below-ground, gravity fed tank (65m long x 35m wide x 6m deep) constructed on 154 (No.) 750mm diameter continuous flight auger (CFA) concrete piles. Other main elements of the project include:

- Storm return pump station integral to the main tank structure and connection of all return storm flows to the existing works inlet.
- Pump mixers.
- Interconnecting pipework between the existing storm tanks and the new tank.
- Reinforced concrete launder channel.
- Storm overflow.
- Modification to existing storm tank weirs and addition of penstocks to control flows.

- Extension of washdown pipework.
- New MCC and automation and control systems.
- EDM instrumentation.

Suspended solids resilience: In addition to the works above and to assist with suspended solids resilience, further works to install 50 (No.) Integrated Fixed-Film Activated Sludge (IFAS) modules to ensure that suspended solids performance on the existing treatment Stream 1 is sufficient. This will support compliance with the new phosphorus permit standards. The system will enable the relevant aeration lanes to operate at a mixed liquor suspended solids (MLSS) concentration of 2,400 mg/l.

The solution was to be designed for the 2040 horizon, however installation in AMP7/AMP8 will be for the 2030 horizon, but with facility to extend subject to performance and any revised horizon. It will be the largest installation of this type in the country.

Works to facilitate this installation include:

- Retrofit of the existing anoxic and contact zone selector tanks to include a new IFAS MABR module support superstructure.
- Two scour and two process blowers.
- Scour and process air pipes including valves, ancillaries and pipe supports.
- Associated MCC, control system, kiosk, cabling and instrumentation.
- Permanent crane slab to enable installation, removal and maintenance of the modules.

Additional sludge storage: Surplus sludge is pumped from Holdenhurst WRC to Berry Hill Sludge Treatment Centre (STC). As a consequence of dosing with PAC, increased sludge production is anticipated, and therefore 740m³ of additional sludge reception and holding capacity was constructed at the Berry Hill STC. The main elements of works for this include:


- Refurbishment of currently disused tank to provide additional raw sludge reception, including new stainless-steel panels, GRP roof, high-level access platform, mixer system and pipework.
- Refurbishment of existing SAS/raw mixing tank including new stainless-steel panels, GRP roof, high-level access platform, mixer system and pipework.
- New 740m³ stainless steel SAS reception tank, GRP roof, new piled foundation and base slab, mixer system and pipework.
- Two raw sludge transfer pumps, two SAS transfer pumps and replacement of existing SAS GBT feed pumps.
- Modifications to rising mains.
- Associated MCCs, control system, kiosk, cabling and instrumentation.

Project delivery

Project Delivery was managed by YTL Construction (Wessex Water) under its external workstream comprising:

- **Design consultants:** Mott MacDonald
- **Principal & civils contractor:** Envolve Infrastructure
- **MEICA contractor:** Trant Engineering
- **Automation & Commissioning:** YTL Construction
- **Berry Hill sludge capacity civils & MEICA:** Galliford Try

The collaborative approach by all delivery partners and industry specialists enabled this £30m capital investment programme of works to be effectively developed from optioneering, through detailed design, construction and commissioning to achieve successful delivery of this complex and challenging project in little over 24 months.



3D model showing the proximity of the existing assets - Courtesy of YTL



Storm Tank 15: CFA piling installation - Courtesy of YTL



Storm Tank 15 (July 2024) - Courtesy of Envolve Infrastructure



Storm Tank 15 (July 2024) - Courtesy of Envolve Infrastructure

Holdenhurst WRC & Berry Hill STC: Supply chain - key participants

Holdenhurst WRC

CFD Modelling: Invent AG
Dewatering design & CAT3 check: Richter Associates
Dewatering subcontractor: Dewatering Services Ltd
Piling subcontractor: Balfour Beatty Ground Engineering
Cofferdam & temporary works designer: JIG Consulting Engineers
Temporary works/shoring: MGF Ltd
Temporary works/piling: SPI Piling
Coring & demolition: Southern Counties Drilling Solutions
Reinforced concrete subcontractor: Carney Construction Ltd
Reinforcement: ROM Reinforcements
Specialist sub-designer/IFAS membrane units: OxyMem Ltd

Steelwork subcontractor: Woodhams Group
MCC, panel & kiosk: GPS Group
Valves: AVK UK Ltd
Actuated penstocks: Glenfield Invicta
Storm return pumps: Xylem Water Solutions
Storm mixer pumps: KSB Pumps
Lifting gantry: Able Lifting
Chemical storage tanks: Forbes Group
Pipework: Saint Gobain PAM UK
Pipework: Frazer Civils Infrastructure
Concrete: Avon Material Supplies Ltd

Berry Hill STC

Civils sub-contractor: Bartlett Contractors Ltd
Piling design & installation: Suttle Projects Ltd
Electrical installation: Spectrum Electrical Group
Stainless steel tanks: Hayes GFS Ltd
Tank mixer pump supplier: Hidrostat

Pumps: Nov Process & Flow Technologies UK Ltd
MCC, panel & kiosk: GPS Group
Stainless steel pipe fabrications: ABC Stainless Ltd
Access platform fabrications: Atom Fabs Ltd
Trace heating & lagging: Jade Insulation

Design & ECI

Through early contractor involvement (ECI) during the design phase, Envolve Infrastructure and Trant Engineering were able to use their specialist sector knowledge to guide the project team through key constructability decisions.

Assessments were made with regards to safety, quality, time and cost aligning with all partners underlying business ethos.

At the outset, Envolve Infrastructure worked closely with all stakeholders to develop a construction methodology for the storm tank. Numerous options were considered for providing the circa 9,000m³ of additional storage including caisson shafts, secant

piling, precast concrete tanks and variables of an in situ RC tank, and a detailed comparison report was undertaken for all methods. The concluding findings were that a 65m x 35m x 6m rectangular in situ RC tank would provide the optimum solution due to the challenging ground conditions, time constraints, ongoing operability and whole-life cost.

In addition, further crucial decisions were considered in relation to the storm return pumping station; initially options were presented for a standalone construction, however Envolve Infrastructure worked with the stakeholders to develop a solution of an integrated pump station which generated both programme and costs efficiencies.



Storm Tank 15 (July 2024) - Courtesy of Envolve Infrastructure

Challenges & mitigation

Stormwater tank construction: existing ground conditions: Ground conditions at Holdenhurst WRC are inherently poor, consisting of a high-water table and the presence of running sands.

The large-scale cofferdam required for the stormwater holding tanks posed significant geotechnical challenges and demanded a specialised design to ensure safe and effective excavation.

Envolve Infrastructure undertook additional ground investigation including a reduced size trial cofferdam. The ECI provided by Envolve Infrastructure throughout the design development stages of the project identified the significant advantage of using a cantilevered sheet pile arrangement rather than a traditional top frame support of the cofferdam.

The proposal allowed for the cofferdam sheet piles to be propped at tank base slab level by filling the 2.5m gap between the sheet piles and base slab with mass concrete, therefore allowing the removal of the top frame, and construction of the tank walls in a single lift rather than two, providing an enhanced solution in terms of safety, quality, time and cost.

Groundwater: Due to a high-water table and high permeability of the ground, Richter Associates were consulted to advise on dewatering requirements to enable the construction of the storm tank.

Pump tests were undertaken to inform the dewatering design and for inclusion in the EA Abstraction License application. The final design catered for an abstraction rate of 60-100 l/s, targeting a drawdown level of approximately 8m below ground level. It comprised of 20 wells around the internal perimeter of the cofferdam, together with three internal passive wells to depressurize the Poole Formation.

Groundwater was delivered to a booster pump station by 20 down hole pumps, which then pumped the groundwater to the discharge location. The pumping arrangement had to be robust, with duty/standby pumps as well as back-up power supplies.

Strict EA permit conditions required the discharged water to meet set levels for turbidity, pH and flow rate. The dewatering discharge was via the storm overflow pipework to the River Stour and, while the trials indicated that the discharge should not present a pollution issue, real-time water quality and CCTV monitoring linked to remote alarms and automatic shutdown was provided at the point of discharge to the storm overflow pipework to mitigate the risk of pollution events occurring.

The dewatering system was in place for 9 months with 20 pumps discharging 100 l/s, 24 hours/day and worked flawlessly over the duration of construction, providing ideal conditions for the construction of the new stormwater storage tank.

Existing assets: Adjacent to the new stormwater storage tank are three 42" spun iron feed syphon pipes, located approximately 3m away from the main cofferdam at an invert level of 3.5m below ground level. These are critical assets for Wessex Water and any compromise could lead to loss of incoming flows and a major pollution event.

A detailed asset protection plan was drawn up and maintained throughout construction, covering installation and removal of the cofferdam sheet piles, CFA piling works, plant/construction loadings, deflection of the cofferdam during excavation and settlement due to dewatering activities.

The pipes were assessed by CCTV and non-destructive testing to determine their condition, and industry specialists employed to establish permissible movement and changes in stress/strain.



Storm Tank 15: Frame removal - Courtesy of YTL



Storm Tank 15 (January 2025) - Courtesy of YTL



Storm Tank 15 (March 2025) - Courtesy of YTL



Storm Tank 13/14 overflow & connections
Courtesy of Envolve Infrastructure

The pipes were monitored throughout construction using the following techniques:

Position/ movement	Stress/strain gauges	Down hole extensometers
Vibration	Down hole inclinometers	Groundwater level

Throughout the excavation process, a series of monitoring methods were deployed including inclinometers and survey monitoring to measure movement of the cofferdam due to dewatering and the cofferdam construction sequence.

Alarm levels were set at approximately 70% of the assessed maximum, and with any exceedance causing construction to pause and assess impact on the syphons.

Due to the rigorous monitoring plan and tight control during construction, the stormwater storage tank was completed without incident and no exceedances recorded.

IFAS MABR module steelwork superstructure: To suspend the IFAS MABR modules within the existing anoxic and contact zone selector tanks, YTL Construction commissioned Mott MacDonald to develop a steel superstructure. This design was required to take into account of and manage the complex interactions between the existing tank structure, capacity, the module loading and placement, ancillary elements and the superstructure itself.

Significant consideration was given to the module and walkway placement and layout. This limits potential damage to the modules during installation and removal for maintenance by ensuring sufficient clearances and ensure safe access for operatives to undertake maintenance.

This was undertaken collaboratively with input from the module designers (OxyMem Ltd) and contractor (Trant Engineering), and an iterative design approach was utilised where required between parties.

Interface with existing assets: There have been several challenges associated with the interface with live operational assets including:


- Adjustment of existing storm tank weirs whilst tanks remain live in case of storm event.
- Construction of IFAS MABR steel superstructure within the existing anoxic and contact zone selector tanks requiring temporary over-pumping whilst the treatment stream remains live.

Planning and management of these activities have required liaison between designers, contractors and Client Operations, and also consideration of timing in relation to weather patterns, to ensure the works were completed safely with no impact on the treatment process.

Efficiencies & sustainability

A collaborative approach was adopted throughout the design stages to improve buildability, involving YTL Construction, the design consultants and technical specialists together with early contractor engagement.

YTL Construction's off-site build (OSB) in-house team provided the design, manufacture and supply of pre-assembled standardised equipment. Benefits of this approach are numerous and include improved efficiency and consistency, shorter construction programmes and improved health and safety for workers. The approach can also result in reduced carbon expenditure due to efficiency savings, reduced vehicle movements and reduced site construction time. For this project, the team provided equipment



IFAS steelwork 3D model - Courtesy of YTL

for both of the existing treatment streams such as chemical dosing kiosks, point of application boxes, emergency showers and lighting columns. These were installed on site along with heated chemical storage tanks with working capacity of 65m³ and 40m³, protection bunds and supporting services to provide the new completed chemical dosing facilities.

The image on the right shows an example of the new facilities as shown in the BIM 3D model developed for the project. This utilised items from a 'Standard Products Library' developed by the OSB team, reducing modelling time and improving model standardisation.

The innovative IFAS MABR technology from OxyMem Ltd is also associated with significant efficiencies for the wastewater treatment process. These include energy savings resulting from smaller blowers and preventing wastage of unused oxygen, reduced sludge production due to a less turbulent fluid flow and a reduced footprint due to the ability to suspend the modules into existing tanks.

Environmental/carbon reduction

The importance of reducing the carbon and energy impact of our services on the climate is an important and valuable objective for the strategic partnership between the stakeholders. Civil engineering can also be obstructive to local environments; therefore, the delivery team formulated a strategy to ensure the project left a positive lasting legacy for the local environment and community:

- Inclusion of the Environment Agency into the stakeholder management strategy to plan works through classified Watercourses in line with most appropriate and complementary methods and planned dates.
- Utilising HVO fuel for all plant and equipment.
- Replanting of hedgerows and trees with native species.
- Preservation and protection of local habitats.
- Establishing tree protection zones and safety of trees subject to protection orders.
- Re-use of excavated material on site, reducing both landfill and vehicle movements.
- Off-site manufacturing.

Project completion & summary


To ensure that the regulatory output was achieved and to mitigate against the resultant challenging timescales, the project delivery strategy included advanced procurement and critical enabling works for the major construction elements.

Works started on site in September 2023, and all regulatory outputs were achieved on 30 March 2025. This impressive achievement was due to the collaborative approach to project management, construction, and commissioning by all partners.

At the time of writing (June 2025) the works at Holdenhurst WRC are nearing completion. This complex but ultimately successful project ensures that future development growth can continue in the Bournemouth area with a significant improvement to the treatment process and quality of final effluent.

The project has been delivered to the highest quality and Health & Safety standards and is testimony an aligned project delivery team and wider supply chain.

The editor and publishers would like to thank Joe Edmunds, Programme Manager with YTL Construction (Wessex Water), Elizabeth Keen, Design Coordinator with Mott MacDonald, Ben Norris, Contracts Director with Envolve Infrastructure, Tim Burt, Technical Manager with Envolve Infrastructure, and Neil Allen, Contracts Manager with Trant Engineering, for providing the above article for publication.



3D model of chemical dosing arrangement - Courtesy of YTL



Chemical dosing (Stream 2) delivery & storage bund
Courtesy of Envolve Infrastructure



IFAS steelwork installation - Courtesy of Trant Engineering



IFAS steelwork installation - Courtesy of Trant Engineering